MYSORE DIVISION.

Dated 18th August 1904.

1. Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Mysore Division, up to 15th September 1904, for restoring Oommathur tank, Chamrajnagar Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1905.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Mysore between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 300 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Oommathur tank, Chamrajnagar Taluk, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Sub-Work.	*Particulars of work.*	*Per.*	*Quantity.*
I.—Tracing Bank—			
	Earthwork excavation	C. yd.	5,537
	Do Bank	"	9,413
	Turfing	Sqr.	645·35
	Grade stones	Each.	24
II.—Channel—			
	Channel excavation	C. yd.	14,444
Drop 4'—			
	Earthwork excavation	"	349
	Concrete work	C. ft.	491
	Brick in surki mortar	"	894
	Burnt stone slabs	S. ft.	257
	Rough stone work, new	C. yd.	56
	Chunam plastering	Sqr.	306
	Mile bank and bed grade stones	Lump sum.	
III.—Relieving weir—			
	Earthwork excavation	C. yd.	1,918
	Concrete in surki mortar	C. ft.	2,457
	Brick in surki mortar	"	3,579
	Chunam plastering	Sqr.	11·55
	Painting chunam	"	3·43
	Pins or joggles to body wall	Each.	16
	Rough stone work	C. yd.	114
	Burnt stone slabs	S. ft.	1,344
IV.—Regulating sluice—			
	Earthwork excavation	C. yd.	871
	Concrete in surki mortar	C. ft.	1,248
	Brick in surki mortar	"	2,930
	Burnt stone slabs	S. ft.	1,236
	Chunam plastering	Sqr.	14·39
	Gear rods with fixing	Each	5
	Teakwood shutters for vent with iron fitting, etc.	"	5
	Rough stone work	C. yd.	200
	Teakwood beam	C. ft.	36½
V.—Constructing a 50' Weir, right.—			
	Earthwork excavation	C. yd.	936
	Chunam concrete	C. ft.	1,191
	Burnt brick in surki mortar	"	2,424
	Burnt stone slabs	S. ft.	1,287
	Rough stone work	C. yd.	158
	Chunam plastering	Sqr.	6·21
	Cement pointing	"	7·42
	Levelling the excavated stuff, etc.	C. yd.	936
	Cutting year and date stone	Each	1
Weir, left—Same as right weir.			

V. ARUNACHELLAM, *Executive Engineer.*